


PUMP STATION 134 & 123 FORCE MAIN MAINTENANCE PLAN


OCTOBER 2014

CITY OF HAMPTON

**WASTEWATER OPERATIONS
550 N. BACK RIVER ROAD
HAMPTON, VA**





**676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540**




PROJECT NARRATIVE:

THIS PROJECT INVOLVES THE REPLACEMENT OF APPROXIMATELY 6,500 LF OF EXISTING 10" AND 12" CAST IRON FORCE MAIN AND THE REHABILITATION OF APPROXIMATELY 600 LF OF 10" CAST IRON FORCE MAIN. THE PROJECT IS LOCATED ALONG CHARLTON DR., WESTBROOK DR., AND RIVERDALE DR. IN THE CITY OF HAMPTON. THE FORCE MAIN INSTALLATION WILL BE ACCOMPLISHED BY OPEN CUT METHODS.

SITE PLAN




VICINITY MAP




SHEET INDEX

		Sheet	Number	Sheet	Title
●	–	OCT 2014	C00		COVER
●	–	OCT 2014	C001		GENERAL NOTES
●	–	OCT 2014	C002		REHABILITATION PLAN
●	–	OCT 2014	P001		PLAN & PROFILE
●	–	OCT 2014	P002		PLAN & PROFILE
●	–	OCT 2014	P003		PLAN & PROFILE
●	–	OCT 2014	P004		PLAN & PROFILE
●	–	OCT 2014	P005		PLAN & PROFILE
●	–	OCT 2014	P006		PLAN & PROFILE
●	–	OCT 2014	P007		PLAN & PROFILE
●	–	OCT 2014	P008		PLAN & PROFILE
●	–	OCT 2014	P009		PLAN & PROFILE
●	–	OCT 2014	P010		PLAN & PROFILE
●	–	OCT 2014	D1		HAMPTON DETAILS
●	–	OCT 2014	D2		DETAILS
●	–	OCT 2014	D3		PUMP STATION NO.134
●	–	OCT 2014	ES1		EROSION & SEDIMENT CONTROL NOTES
●	–	OCT 2014	ES2		EROSION & SEDIMENT CONTROL DETAILS
●	–	OCT 2014	T1		TRAFFIC CONTROL NOTES AND DETAILS

DRAWING INDEX LEGEND

[illegible]

PROJECT No.:	068002
---------------------	--------



C000

Layout Tab Name: C001, Images: Base_134.jpg; Rehab_123 - Copy.jpg; , Xrefs: 68002_TBLK.dwg; 68002_X.dwg
Last Saved By:obrien, 9/24/2014 10:47:29 AM
W:\Srvn\JM\Chesapeake\Projects\VA\Hampton_OI\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_GEN.dwg Plotted By:O'Brien, Maxwell Plotted:March 31, 2015, 9:00:42 AM

GENERAL NOTES:

1. WHERE NOTED, "CITY" SHALL BE SHORTHAND NOTATION FOR CITY OF HAMPTON.

2. THE CONTRACTOR SHALL PROVIDE THE CITY FIVE WORKING DAYS NOTICE PRIOR TO COMMENCING WORK ON THE PROJECT. THE CONTRACTOR SHALL COORDINATE WITH BARRY DOBBINS (HAMPTON) AT: (757) 726-2944 AND JIM EWING (WOOLPERT) AT: (OFFICE) (757) 549-5360 OR (CELL) (757) 282-8423. FOR THE PURPOSES OF THESE CONTRACT DOCUMENTS, "ENGINEER" REFERS TO WOOLPERT.

3. NORMAL HOURS OF CONSTRUCTION ARE FROM 7 AM TO 5 PM.

4. THE LOCATION, DEPTHS AND SIZES OF EXISTING UTILITIES SHOWN ON THESE PLANS HAVE BEEN OBTAINED FROM AVAILABLE UTILITY RECORDS AND ARE NOT GUARANTEED. THE CONTRACTOR SHALL CONTACT MISS UTILITY FOR MARKING ASSISTANCE PRIOR TO STARTING ANY CONSTRUCTION ACTIVITIES. THE ENGINEER ASSUMES NO LIABILITY FOR THE CORRECTNESS OF THE DATA PROVIDED BY THE UTILITY OWNERS. THE CONTRACTOR SHALL FIELD VERIFY WITH TEST HOLES THE EXACT LOCATION, ELEVATION, MATERIAL TYPE, ROUNDNESS (AT POINTS OF CONNECTION) AND SIZE OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO ORDERING OF MATERIALS, EXCAVATION, AND INSTALLATION FOR THIS PROJECT. ALL COSTS ASSOCIATED WITH THE ADDITIONAL UNDERGROUND UTILITY LOCATING AND VERIFICATION SHALL BE INCIDENTAL AND INCLUDED IN THE CONTRACTOR BID FOR PROPOSED WORK.

5. THE CONTRACTOR SHALL HAND EXCAVATE WHEN CROSSING EXISTING UTILITIES TO AVOID DAMAGE. WHEN CONSTRUCTING WORK UNDER OR ADJACENT TO EXISTING UTILITIES, PROVIDE ADEQUATE SUPPORT TO PROTECT EXISTING UTILITIES FROM DAMAGE.

6. THE CONTRACTOR SHALL COMPLY WITH ALL PROVISIONS OF THE OVERHEAD HIGH VOLTAGE ACT AND SHALL PROVIDE TEMPORARY SUPPORT TO UTILITY POLES WHERE NECESSARY.

7. IF EXISTING UTILITIES ARE DAMAGED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR IMMEDIATE REPAIR TO PRE-CONSTRUCTION CONDITION AT CONTRACTOR EXPENSE.

8. THE CONTRACTOR SHALL ENSURE ALL UTILITIES REMAIN IN SERVICE DURING CONSTRUCTION, EXCEPT FOR CITY APPROVED OUTAGES. VALVES MAY ONLY BE OPENED AND CLOSED BY OR UNDER THE DIRECT SUPERVISION OF THE OWNER'S PERSONNEL.

9. THE CONTRACTOR SHALL RESTORE ALL EXISTING SITE CONDITIONS (CURBS, SIDEWALKS, DRIVEWAYS, MAILBOXES, ETC.) DAMAGED DURING CONSTRUCTION, TO THEIR PRE-CONSTRUCTION CONDITIONS.

10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND LICENSES REQUIRED BY THE STATE OF VIRGINIA, CITY OF HAMPTON, OR OTHER GOVERNING AGENCIES, AS NECESSARY, TO COMPLETE THIS PROJECT. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL FEES ASSOCIATED WITH OBTAINING THESE PERMITS.

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT INGRESS/EGRESS IS MAINTAINED TO ALL ENTRANCES.

12. THE CONTRACTOR SHALL COORDINATE WITH, AND ARRANGE FOR INSPECTION BY THE ENGINEER.

13. THE CONTRACTOR SHALL COMPLY WITH ALL EROSION AND SEDIMENT CONTROL REGULATORY REQUIREMENTS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.

14. MATERIAL EXCAVATED FROM TRENCHES SHALL BE PLACED ON THE UP-SLOPE SIDE OF THE TRENCH WHEN TRENCHING IN NON-PAVEMENT AREAS, PLACE SILT FENCE ON THE DOWN-SLOPE SIDE OF THE TRENCH.

15. ALL SLOPES AND DISTURBED AREAS SHALL BE FERTILIZED, SEEDED AND MULCHED. THE MAXIMUM ALLOWABLE SLOPE IS 2:1 (HORIZONTAL:VERTICAL). WHERE REASONABLY OBTAINABLE, LESSER SLOPES OF 3:1 OR BETTER ARE TO BE ACHIEVED.

16. THE CONTRACTOR SHALL VERIFY THE ACTUAL FIELD CONDITIONS AND DEPTH AT EACH POINT OF CONNECTION TO EXISTING UTILITIES TO ALLOW ADJUSTMENTS IN THE WORK WITHOUT IMPACTING THE WORK PROGRESSION.

17. THE CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING TREES AND SHRUBS AND OTHER LANDSCAPE FEATURES, UNLESS OTHERWISE NOTED FOR REMOVAL ON THE DRAWING.

18. THE CONTRACTOR SHALL FURNISH ALL MATERIALS, LABOR AND EQUIPMENT AND PERFORM ALL WORK NECESSARY TO COMPLETE ALL WORK AS SHOWN ON THESE PLANS. WORK SHALL BE COMPLETED IN ACCORDANCE WITH APPLICABLE STANDARDS AND CONSTRUCTION SPECIFICATIONS OF HRPDC, VDOT, VDH, THE CITY OF HAMPTON, AND THESE CONTRACT DOCUMENTS.

19. ANY UNUSUAL SUBSURFACE CONDITIONS ENCOUNTERED DURING THE COURSE OF THE WORK SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CITY AND THE ENGINEER.

20. THE CONTRACTOR SHALL CLEAN UP AND RESTORE DISTURBED AREAS IMMEDIATELY UPON COMPLETION OF WORK WITHIN THE AFFECTED AREA.

21. THE CONTRACTOR SHALL PROVIDE UNIFORM (STRAIGHT) GRADE BETWEEN SPOT ELEVATIONS, VALVE BOXES, ETC.

22. ALL EXCAVATION FOR UNDERGROUND PIPE INSTALLATION MUST COMPLY WITH OSHA STANDARDS FOR THE CONSTRUCTION INDUSTRY (29 CFR PART 1926). LIVE GAS LINES EXIST IN MULTIPLE AREAS OF THE PROJECT CORRIDOR, AND IN THE VICINITY OF PROPOSED UTILITY WORK. CONTRACTOR SHALL COMPLY WITH ALL PERTINENT REGULATIONS AND GAS UTILITY PROVIDER REQUIREMENTS FOR WORK IN THE VICINITY OF THESE GAS LINES.

23. CONNECTIONS TO EXISTING UTILITIES SHALL BE MADE AS INDICATED. THE CONTRACTOR SHALL COORDINATE THE SHUTDOWN OF EXISTING AND/OR ACTIVATION OF PROPOSED UTILITIES WITH THE CITY FOURTEEN (14) DAYS PRIOR TO ANTICIPATED DATE OF CHANGEOVER AND OR TIE IN. A REPRESENTATIVE FROM THE CITY SHALL BE PRESENT DURING TIE INS TO EXISTING UTILITY LINES.

24. SUBMIT A PLAN OF OPERATION TO THE CITY FOR APPROVAL NO LESS THAN TWENTY ONE (21) DAYS PRIOR TO ANY CONNECTION TO EXISTING FACILITIES REQUIRING OUTAGES/DISRUPTION OF SERVICE. THIS PLAN OF OPERATION SHALL CLEARLY INDICATE WHICH EXISTING LINES WILL REQUIRE OUTAGES, PROPOSED METHODS AND PLAN OF CONNECTION, TIMEFRAME REQUIRED TO PERFORM WORK, INDICATION THAT NECESSARY LABOR, EQUIPMENT, AND MATERIALS WILL BE AVAILABLE TO COMPLETE THE WORK WITHIN THE SPECIFIED TIMEFRAME, AND ANY OTHER PERTINENT INFORMATION SPECIFIC TO THE PROPOSED WORK ACTIVITY. THE PLAN OF OPERATION SHALL ALSO INCLUDE A CONTINGENCY PLAN TO ADDRESS ANY POTENTIAL COMPLICATIONS OR CIRCUMSTANCES THAT COULD AFFECT COMPLETION OF THE WORK WITHIN THE SPECIFIED TIMEFRAME. PUBLIC NOTIFICATION AND PREPARATION FOR OUTAGES SHALL BE PROVIDED BY THE CITY.

25. NO BELLS OF PROPOSED UTILITIES SHALL BE LOCATED UNDERNEATH DRAINAGE/UTILITY LINES AT CROSSINGS. FULL LENGTHS OF PROPOSED LINE SECTIONS SHALL BE CENTERED AT CROSSINGS.

26. THE CONTRACTOR SHALL UTILIZE STRAPS INSTEAD OF CHAINS, CABLES, OR UNPADDED FORKS TO HANDLE PIPE.

27. THE CONTRACTOR SHALL PROTECT ALL DISTURBED AREAS FROM WATER DAMAGE. ALL UNSUITABLE MATERIALS THAT ARE THE RESULT OF THE CONTRACTOR'S ACTION SHALL BE REMOVED AND REPLACED WITH LIKE MATERIALS AT THE CONTRACTOR'S EXPENSE.

28. ALL UTILITY PIPE, LININGS, VALVES AND WORK SHALL CONFORM TO HAMPTON ROADS PLANNING DISTRICT COMMISSION (HRPDC) REGIONAL CONSTRUCTION STANDARDS.

29. THE CONTRACTOR IS RESPONSIBLE FOR KNOWING AND UNDERSTANDING ALL PERTINENT VIRGINIA DEPARTMENT OF HEALTH (VDH) WATERWORKS REGULATIONS.

30. CONTRACTOR SHALL PROVIDE ALL EQUIPMENT, MATERIALS, AND PERSONNEL AS REQUIRED TO DEWATER TRENCHES AND EXCAVATIONS DURING INSTALLATION OF NEW PIPE AND STRUCTURES.

31. CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT TREE PRESERVATION AND PROTECTION INDICATED ADEQUATELY PROTECTS DELINEATED TREES AND ROOT STRUCTURE. IF TREE ROOT STRUCTURE AFFECTED BY EXCAVATIONS, CONTRACTOR SHALL RELOCATE OR REPLACE THE TREE AT THE DISCRETION OF THE CITY. IF TREE REPLACEMENT IS REQUIRED, REPLACE WITH TREE OF SAME DIAMETER. IF RELOCATION IS REQUIRED, CONTRACTOR SHALL HAVE TREE RELOCATED BY SUB-CONTRACTOR SPECIALIZING IN THIS TYPE OF WORK.

32. TREE SHALL BE RELOCATED TO LOCATION AS DIRECTED BY THE CITY. TREE HEALTH SHALL BE GUARANTEED FOR A MINIMUM OF FIVE YEARS. TREES INDICATED TO BE REPLACED BY THE CITY SHALL ALSO CONFORM TO THESE REQUIREMENTS.

33. CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO OWNER/RESIDENT OF PROPERTY ADJACENT TO A DEVELOPMENT OR OFFSITE IMPACTED AREA 30 DAYS PRIOR TO COMMENCEMENT OF WORK UNLESS OTHERWISE DIRECTED BY THE CITY. FAILURE TO PROVIDE MINIMUM NOTICE SHALL RESULT IN SUSPENSION OF WORK.

34. ANY REVISION TO THE APPROVED TRAFFIC CONTROL PLANS SHALL BE COORDINATED THROUGH THE ENGINEER AND THE CITY.

35. CITY OF HAMPTON DEPARTMENT OF PUBLIC WORKS OPERATIONS-STREET OPERATIONS 550 NORTH BACK RIVER ROAD, HAMPTON, VA 23669 CONTACT INFORMATION IS AS FOLLOWS:
DEPARTMENT OF PUBLIC WORKS: (757) 726-2914
FAX: (757) 726-2822
OUTSIDE NORMAL WORKING HOURS: (757) 727-8311

36. A PRECONSTRUCTION MEETING WITH THE CITY IS REQUIRED. CONTACT THE CITY (ZANDY AMOR) AT (757) 726-2914 TO SCHEDULE THIS MEETING.

37. IF WATER SERVICE LINES ARE DAMAGED, THEY MUST BE REPLACED FROM THE METER BOX TO THE MAIN. SPLICES ARE NOT ACCEPTABLE.

38. JOINT DEFLECTION SHALL NOT EXCEED 80% OF THE MANUFACTURER'S RECOMMENDED MAXIMUM OR AWWA MAXIMUM, WHICHEVER IS LESS.

DRAINAGE NOTES:

1. TEMPORARY DRAINAGE DURING CONSTRUCTION TO BE PROVIDED BY THE CONTRACTOR TO RELIEVE AREAS THAT MAY CAUSE DAMAGE TO ROADWAY, OR PROTECT THE INTEGRITY OF THE SUBGRADE. THE CONTRACTOR IS RESPONSIBLE FOR DETERIORATION OF SUBGRADE CAUSED BY NEGLIGENT CONSTRUCTION METHODS AND INADEQUATE DRAINAGE. FAILURE TO PROVIDE TEMPORARY DRAINAGE WILL RESULT IN THE CONTRACTOR'S RESPONSIBILITY TO CORRECT DAMAGED SUBGRADE AT THE CONTRACTOR'S EXPENSE.

2. PROVIDE TEMPORARY DRAINAGE OF PAVEMENT AND ADJACENT PROPERTY TO PREVENT STANDING WATER.

3. WHENEVER SEDIMENT-LADEN WATER IS REMOVED FROM A CONSTRUCTION SITE BY MEANS OF PUMPING, A TEMPORARY SETTLING AND FILTERING DEVICE SHALL BE USED TO FILTER THE SEDIMENT-LADEN WATER PRIOR TO THE WATER BEING DISCHARGED OFF-SITE

BYPASS PUMPING:

1. THE CONTRACTOR SHALL HAVE AT LEAST TWO BYPASS PUMPS ON SITE. PUMPS SHALL BE SIZED TO HANDLE PEAK FLOW WITH 100% REDUNDANCY. BACKUP PUMPS SHALL BE AVAILABLE FOR REPLACEMENT SHOULD THE PRIMARY BYPASS PUMPS FAIL.

2. THE CONTRACTOR IS TO MONITOR AND CONTROL THE BYPASS PUMPING OPERATION INCLUDING, BUT NOT LIMITED TO, THE WATER LEVELS IN THE BYPASS MANHOLES.

3. THRUST RESTRAINTS AND OTHER REQUIREMENTS RELATED TO THE BYPASS LINES ARE TO BE DETERMINED AND ADJUSTED BY THE CONTRACTOR WITH REGARD TO EACH BYPASS ROUTE.

PUMP STATION BYPASS

- A. THE CONTRACTOR SHALL SUBMIT A FLOW CONTROL AND SEWAGE BYPASSING ARRANGEMENT PLAN TO THE ENGINEER FOR REVIEW AND APPROVAL AT LEAST TWO WEEKS (14 CALENDAR DAYS) PRIOR TO COMMENCING WORK. FLOW CONTROL INCLUDES, BUT IS NOT LIMITED TO; PLUGGING AND BYPASS PUMPING, THE PLAN MUST BE SPECIFIC AND COMPLETE, INCLUDE ALL LAYOUTS OF THE BYPASS PIPING, AND SHALL INCLUDE, BUT NOT BE LIMITED TO, THE FOLLOWING DETAILS:
1. EQUIPMENT LIST/SITE PLAN WITH EQUIPMENT LAYOUT.
2. MONITORING PLAN.
3. DESCRIPTION OF EQUIPMENT OPERATIONAL CONTROLS.
4. SPILL CONTINGENCY PLANS AND PROTECTION AGAINST PIPE BREAKS.
5. METHOD OF CONNECTING TO DISCHARGE FORCE MAIN.
6. SIZE, LENGTH, MATERIAL, AND METHOD OF INSTALLATION FOR SUCTION AND DISCHARGE PIPING.
7. METHOD OF NOISE CONTROL FOR EACH PUMP AND/OR GENERATOR.
8. CONSTRUCTION SEQUENCE.
9. BYPASS TIME DURATION FOR THE FORCE MAIN INSTALLATION AND PUMP STATION PIPING MODIFICATIONS.

B. BYPASSED FLOW MUST BE DISCHARGED TO THE PROP. SANITARY SEWER FORCE MAN AND SHALL BE CONTINUOUS AND UNINTERRUPTED.

C. THE CONTRACTOR SHALL SUPPLY THE NECESSARY PUMPS, CONDUITS, ENGINE CONTROLS, LEVEL CONTROLS, AND OTHER EQUIPMENT TO DIVERT THE FLOW OF SEWAGE IN ACCORDANCE WITH THE APPROVED PLAN. THE CONTRACTOR SHALL HAVE BACKUP EQUIPMENT ON SITE AND CONNECTED TO THE PRIMARY PUMPING SYSTEM. THE BACKUP EQUIPMENT SHALL BE THE SAME AS THE PRIMARY PUMPING SYSTEM. THE PUMPING/BYPASS SYSTEM SHALL BE ADEQUATE IN SIZE TO HANDLE THE EXISTING PEAK FLOWS DESIGN PUMPING RATE = 1,650 GPM, AVERAGE DAILY INFLOW = 660 GPM. THE CONTRACTOR SHALL SELECT PUMPING/BYPASSING EQUIPMENT THAT WILL NOT HAVE EXCESSIVE NOISE LEVELS AND SHALL BE RESTRICTED TO A MAXIMUM OF SIXTY DECIBELS (60 DB) AT A DISTANCE OF FIFTY FEET (50'). THE CONTRACTOR SHALL ALSO BE REQUIRED TO HAVE ON SITE A 500 GALLON FUEL CUBE TO SUPPORT THE BYPASS PUMPS.

D. THE CONTRACTOR SHALL ALSO FURNISH THE LABOR AND SUPERVISION TO SET UP, OPERATE AND MAINTAIN, AND CONTINUOUSLY MONITOR THE PUMPING/BYPASS SYSTEM FROM THE TIME THE PUMP STATION IS TAKEN OUT OF SERVICE UNTIL IT IS RETURNED TO SERVICE. BYPASS CONTRACTOR SHALL BE CAPABLE OF RESPONDING TO MAINTENANCE NEEDS IN TWO HOURS OR LESS.

E. FLOW CONTROL PRECAUTIONS
1. WHEN FLOW IS BYPASSED BY THE CONTRACTOR, HE SHALL TAKE PRECAUTIONS TO PROTECT THE PUBLIC HEALTH AND TO PROTECT THE SEWER LINES FROM DAMAGE THAT MIGHT RESULT FROM SEWER SURCHARGING. THE CONTRACTOR SHALL TAKE PRECAUTIONS TO INSURE THAT SEWER FLOW CONTROL OPERATIONS DO NOT CAUSE FLOODING OR DAMAGE TO PUBLIC OR PRIVATE PROPERTY BEING SERVED BY THE SEWERS INVOLVED AND HE SHALL BE RESPONSIBLE FOR ANY DAMAGE RESULTING FROM HIS FLOW CONTROL OPERATIONS.
2. DURING THE BYPASS PUMPING PERIOD NO LIQUID OR SOLID MATTER SHALL BE ALLOWED TO BE DISCHARGED ON THE GROUND, SWALE, ROAD, STORMWATER DRAINAGE SYSTEM, OR OPEN ENVIRONMENT. THE CONTRACTOR SHALL PROTECT ALL PUMPS, CONDUIT AND OTHER EQUIPMENT USED FOR BYPASS PUMPING FROM TRAFFIC DAMAGE.
3. SHOULD ANY LIQUID OR SOLID MATTER FROM THE SEWER COLLECTION SYSTEM BE SPILLED, DISCHARGED, LEAKED, OR OTHERWISE DEPOSITED TO THE OPEN ENVIRONMENT AS A RESULT OF THE CONTRACTOR'S FLOW CONTROL OPERATIONS, HE SHALL IMMEDIATELY CLEANUP AND DISINFECT THE AFFECTED AREA AND ASSUME ALL COSTS ASSOCIATED WITH SAME. THE CONTRACTOR SHALL ALSO NOTIFY THE ENGINEER, HAMPTON, AND THE APPROPRIATE REGULATORY AGENCIES AND PERFORM REQUIRED CLEANUP OPERATIONS AT NO ADDITIONAL COST TO THE OWNER.

SUGGESTED SEQUENCE OF CONSTRUCTION:

1. OBTAIN REQUIRED PERMITS FROM THE CITY OF HAMPTON.

2. ATTEND PRECONSTRUCTION MEETING WITH THE ENGINEER AND THE CITY OF HAMPTON.

3. NOTIFY AFFECTED PROPERTY OWNERS.

4. ESTABLISH EROSION AND SEDIMENT CONTROLS.

5. ESTABLISH MAINTENANCE OF TRAFFIC CONTROLS.

PUMP STATION 134 FM

6. INSTALL PROPOSED FORCE MAIN FROM APPROXIMATE STATION 0+05 AT PS 134 TO 53+90. DO NOT MAKE CONNECTIONS TO PUMP STATION OR EXISTING 10" FORCE MAIN. INSTALL AND CLOSE PROPOSED GATE VALVE ON BRANCH SIDE OF TEE AT STATION 44+27.

7. INSTALL PROPOSED EPC PIPING AND VALVE AT EPC TEE. CLOSE VALVE.

8. PERFORM PRESSURE TEST ON ENTIRE SECTION OF PIPELINE.

9. ESTABLISH BYPASS PUMPING OPERATIONS AT PS 134.

10. COORDINATE SHUT DOWN OF PS 134 WITH CITY OF HAMPTON PERSONNEL.

11. COMPLETE PROPOSED PIPING IMPROVEMENTS WITHIN PS 134 DRYWELL. CONNECT TO FORCE MAIN PIPING OUTSIDE OF STATION.

12. COORDINATE CLOSING OF VALVE AT HRSD CONNECTION ALONG MERCURY BLVD. CONNECT PIPING TO 10" FORCE MAIN, APPROXIMATE STATION 54+12.

13. REMOVE BYPASS PUMP OPERATIONS AT PS 134 AND OPEN VALVE AT HRSD CONNECTION. VISUALLY INSPECT CONNECTIONS FOR LEAKS.

PUMP STATION 123 FM

14. INSTALL PROPOSED FORCE MAIN FROM APPROXIMATE STATION 10+65 TO APPROXIMATE STATION 0+09. DO NOT MAKE CONNECTIONS TO PROPOSED VALVE OR PUMP STATION.

15. INSTALL AND CLOSE PROPOSED GATE VALVE ON DOWNSTREAM SIDE OF TEE AT STATION 0+73. PERFORM PRESSURE TEST ON THIS SECTION OF PIPELINE. AFTER SUCCESSFUL PRESSURE TEST, CONNECT PIPE TO GATE VALVE AT BRANCH CONNECTION TO PS 134 FM.

16. COORDINATE SHUT DOWN OF PS 123 WITH CITY OF HAMPTON PERSONNEL. COORDINATE CLOSING OF VALVE AT HRSD CONNECTION ALONG MERCURY BLVD.

17. CONNECT PIPING TO 10" FORCE MAIN AT PS 123.

18. OPEN GATE VALVE AT BRANCH CONNECTION TO PS 134 FORCE MAIN AND TURN ON PUMPS AT PS 123. VISUALLY INSPECT CONNECTIONS FOR LEAKS.

PUMP STATION 123 FM REHABILITATION

19. CCTV AND CLEAN EXISTING PS 123 FORCE MAIN.

20. COMPLETE REHABILITATION OF FORCE MAIN BY CIPP METHODS.

21. PERFORM PRESSURE TEST ON THIS SECTION OF PIPELINE. AFTER SUCCESSFUL PRESSURE TEST, CONNECT PIPE TO VALVE ON DOWNSTREAM SIDE OF TEE AT STATION 0+73. RECONNECT PIPE TO VALVE AT HRSD CONNECTION.

PROJECT CLOSEOUT

22. COMPLETE PAVEMENT AND RIGHT OF WAY RESTORATION AS INDICATED ON THE DRAWINGS.

23. REMOVE TRAFFIC CONTROL MEASURES.

24. REMOVE EROSION AND SEDIMENT CONTROL MEASURES AFTER DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED.

PUMP STATION SAFETY NOTES:

1. KEY CREW MEMBERS FROM CONTRACTR AND SUB-CONTRACTOR (IF APPLICABLE) WILL BE REQUIRED TO HAVE A SAFETY BRIEFING ON SITE PRIOR TO ENTERING THE PUMP STATION; THIS WILL BE DONE BY HAMPTON SAFETY PERSONNEL WHICH WILL REQUIRE COORDINATION ROUGHLY ONE WEEK PRIOR TO THE MEETING.

2. PUMP STATION KEYS (IF APPLICABLE) WILL BE ISSUED TO THE CONTRACTOR AS NEEDED. CONTRCTOR WILL BE REQUIRED TO CONTACT KEVIN JACKSON AT CITY OF HAMPTON (757-727-8408) DAILY AS THEY ARE WORKING IN THE PUMP STATION AS WELL AS SIGNING IN ON THE SIGN-IN SHEET LOCATED AT THE PUMP STATION.

3. THE CONTRACTOR WILL BE REQUIRED TO HAVE THEIR OWN CONFINED SPACE PERSONNEL AND PERMIT.

COMMUNALTY OF VIRGINIA

JAMES EWING

Lic. No. 031109

10-13-14

PROFESSIONAL ENGINEER

REVISION

No.

DATE

PROJECT No: 068002

DATE 10/2014

DES. TD/MM

DR. MOB

CKD. JBE

676 Independence Parkway

Suite 100

Chesapeake, VA 23320

757.549.3549

FAX: 757.549.3540

WOOLPERT

DESIGN/CONSTRUCTION/INFRASTRUCTURE

PUMP STATION 134 & 123

FORCE MAIN MAINTENANCE PLAN

CITY OF HAMPTON, VIRGINIA

PUBLIC WORKS



GENERAL NOTES

SHEET NO.

C001

BEFORE YOU DIG, TO MISS THE UTILITIES
CALL
811
MISS UTILITY OF VIRGINIA

Layout Tab Name: C002, Images: Base_134.jpg: Rehab_123 - Copy.jpg: . Xrefs: 68002_TBLK.dwg; 68002_X.dwg
Last Saved By:brien, 9/24/2014 10:47:29 AM
W:\Srin\IM\Chesapeake\Projects\VA_Hampton_CI\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_GEN.dwg Plotted By:O'Brien, Maxwell Plotted:March 31, 2015, 9:00:51 AM




No.	DATE	REVISION

PROJECT No:	068002
DATE	10/2014
DES. TO/MM	
DR. MOB	
CKD. JBE	


676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540

WOOLPERT
DESIGN / CONSULTING / INFRASTRUCTURE




GENERAL NOTES:

1. THE CONTRACTOR SHALL NOTIFY THE CITY IN THE EVENT THAT ACCESS TO THE CITY'S UTILITY EASEMENT IS NEEDED. THE CITY WILL COORDINATE WITH RESIDENTS FOR ACCESS.
2. THE CONTRACTOR SHALL CCTV AND CLEAN THE EXISTING FORCE MAIN IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. HEAVY CLEANING SHALL BE PAID FOR SEPARATELY, AS DIRECTED BY THE CITY.
4. THE LOCATION, SIZE AND MATERIAL OF EXISTING UTILITIES SHOWN ON THESE PLANS IS BASED ON AVAILABLE UTILITY RECORDS AND CITY OF HAMPTON GIS INFORMATION. THE CONTRACTOR SHALL VERIFY UTILITY SIZE, MATERIAL AND ROUNDNESS (AT POINTS OF CONNECTION) PRIOR TO ORDERING MATERIALS. ALL COSTS ASSOCIATED WITH UTILITY VERIFICATION SHALL BE INCIDENTAL AND INCLUDED IN THE PRICE OF THE BID ITEM.



CONNECTION TO EXISTING FM
(NOT TO SCALE)




**PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN**

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS

REHABILITATION PLAN


SHEET NO.
C002

NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM





NOTE:
ALL DI FITTINGS AND RESTRAINED
PIPING SHALL BE DOUBLE-THICKNESS
WRAPPED WITH POLYETHYLENE
ENCASEMENT.

NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606) [PARKS
DEPARTMENT] TO COORDINATE WORK
IN THE VICINITY OF TREES.



PROFILE VIEW: CHARLTON FM — P002

[illegible]

PROJECT No:	068002
DATE	10/2014
DES.	TD/MM
DR.	MOB
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540




**PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN**

PUBLIC WORKS



PLAN & PROFILE

SHEET NO.

P002



NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606) [PARKS
DEPARTMENT] TO COORDINATE
WORK IN THE VICINITY OF TREES.



PROJECT No:	No.	DATE	REVISION
068002			
DATE		10/2014	
DES.		TD/MM	
DR.		MOB	
CKD.		JBE	

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540




PUMP STATION 134 & 123 FORCE MAIN MAINTENANCE PLAN

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS


PLAN & PROFILE

SHEET NO.

P003




PROFILE VIEW: CHARLTON FM - P004




NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606)
[PARKS DEPARTMENT] TO
COORDINATE WORK IN THE
VICINITY OF TREES.

Layout Tab Name: P005, Images: DSCN3021.JPG; .Xrefs: 68002_TBLK.dwg; 68002_X.dwg; 68002_U.dwg
Last Saved By:obrien, 3/31/2015 8:49:47 AM
W:\Srvr\IM\Chesapeake\Projects\VA_Hampton_C\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_T&P.dwg Plotted:March 31, 2015, 9:03:26 AM



NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM




NOTE:
ALL DI FITTINGS AND RESTRAINED
PIPING SHALL BE DOUBLE-THICKNESS
WRAPPED WITH POLYETHYLENE
ENCASEMENT.



PROFILE VIEW: CHARLTON FM - P005



NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606) [PARKS
DEPARTMENT] TO COORDINATE
WORK IN THE VICINITY OF TREES.



REVISION

No. DATE

PROJECT No: 068002

DATE 10/2014
DES. TD/MM
DR. MOB
CKD. JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540



PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS



PLAN & PROFILE

SHEET NO.



P005

Layout Tab Name: P006, Images: DSCN3021.JPG; . Xrefs: 68002_TBLK.dwg; 68002_X.dwg; 68002_U.dwg
Last Saved By: brien, 3/31/2015 8:49:47 AM
W:\Srin\IM\Chesapeake\Projects\VA_Hampton_CI\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_T&P.dwg Plotted March 31, 2015, 9:03:43 AM
(SEE SHEET P005)

NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM



PROFILE VIEW: CHARLTON FM — P006



REVISION	No.	DATE


PROJECT No:	068002
DATE	10/2014
DES. TD/MM	
DR. MOB	
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540

WOOLPERT
DESIGN | GEOTECHNICAL | INFRASTRUCTURE


PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN
CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS
PLAN & PROFILE

NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM





NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606) [PARKS
DEPARTMENT] TO COORDINATE
WORK IN THE VICINITY OF TREES.

NOTE:
ALL DI FITTINGS AND RESTRAINED
PIPING SHALL BE DOUBLE-THICKNESS
WRAPPED WITH POLYETHYLENE
ENCASEMENT.




PROFILE VIEW: CHARLTON FM — P007



PROJECT No:	No.	DATE	REVISION
068002			
DATE 10/2014			
DES. TD/MM			
DR. MOB			
CKD. JBE			

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540



PUMP STATION 134 & 123 FORCE MAIN MAINTENANCE PLAN

PUBLIC WORKS
PLAN & PROFILE



SHEET NO.

P007



Layout Tab Name: P007, Images: DSCN3021.JPG, Xrefs: 68002_TBLL.dwg; 68002_X.dwg; 68002_U.dwg
Last Saved By: obrien, 3/31/2015 8:49:47 AM

Layout Tab Name: P008, Images: DSCN3021.JPG; . Xrefs: 68002_TBLK.dwg; 68002_X.dwg; 68002_U.dwg
Last Saved By:obrien, 3/31/2015 8:49:47 AM
W:\Srin\IM\Chesapeake\Projects\VA_Hampton_CI\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_T&P.dwg Plotted March 31, 2015, 9:04:18 AM

NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM



PROFILE VIEW: CHARLTON FM – P008



REVISION	DATE	No.

PROJECT No:	068002
DATE	10/2014
DES. TO/MM	JBE
DR. MOB	JBE
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.548.3540

WOOLPERT
DESIGN (GEOTECHNICAL) INFRASTRUCTURE



**PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN**

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS


PLAN & PROFILE

SHEET NO.
P008


NOTE:
ABANDON ALL VALVES
AND ARV'S (TYP.) ON
THE EXISTING 12" FM



PROFILE VIEW: RIVERDALE FM - P009



NOTE:
CONTRACTOR TO CONTACT MIKE
DIEBLER (757-592-0606) [PARKS
DEPARTMENT] TO COORDINATE WORK
IN THE VICINITY OF TREES.



PROJECT No:	068002
DATE	10/2014
DES. TO/MM	
DR. MOB	
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540

WOOLPERT
DESIGN | GEOTECHNICAL | INFRASTRUCTURE



PUMP STATION 134 & 123 FORCE MAIN MAINTENANCE PLAN

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS

PLAN & PROFILE

SHEET NO.

P009











PUBLIC WORKS

PLAN & PROFILE

P010

Layout Tab Name: D1. Images: 68002_TBLK.dwg
Last Saved By:brien, 10/10/2014 9:40:35 AM
W:\Srin\IM\Chesapeake\Projects\VA_Hampton_C\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_DET.dwg Plotted:March 31, 2015, 9:05:18 AM



REVISION	DATE	No.

PROJECT NO:	068002
DATE	10/20/14
DES.	TO/MM
DR.	MOB
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.548.3540





WOOLPERT
DESIGN / CONSULTING / INFRASTRUCTURE

PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN
CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS
HAMPTON DETAILS

SHEET NO.

D1

Layout Tab Name: D2, Images: , Xrefs: 68002_TBLK.dwg
Last Saved By:obrien, 10/10/2014 9:40:35 AM
W:\Swin\IM\Chesapeake\Projects\VA_Hampton_C\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_DET.dwg Plotted By:O'Brien, Maxwell Plotted:March 31, 2015, 9:05:20 AM



REVISION	DATE	No.

PROJECT No:	068002
DATE	10/2014
DES.	TD/MM
DR.	MOB
CND.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540

WOOLPERT
DESIGN / CONSULTING / INFRASTRUCTURE

**PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN**

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS

DETAILS

SHEET NO.
D2



Layout Tab Name: ES1, Images: , Xrefs: 68002_TBLK.dwg
Last Saved By:tsichenkov, 9/3/2014 1:56:46 PM
W:\Srin\IM\Chesapeake\Projects\VA_Hampton_CI\68002_SewerSanitarySystem\Data\Rehab Construction Plans\PS 134&123 FM Replacement\CAD\68002_E&S.dwg Plotted By:O'Brien, Maxwell Plotted:March 31, 2015, 9:05:36 AM

EROSION AND SEDIMENT CONTROL MINIMUM STANDARDS:

MS-1 Permanent or temporary soil stabilization shall be applied to denuded areas within seven (7) days after final grade is reached on any portion of the site. Temporary soil stabilization shall be applied within seven (7) days to denuded areas that may not be at final grade but will remain dormant for longer than thirty (30) days. Permanent stabilization shall be applied to areas that are to be left dormant for more than one (1) year.

MS-2 During construction of the project, soil stockpiles and borrow areas shall be stabilized or protected with sediment trapping measures. The applicant is responsible for the temporary protection and permanent stabilization of all soil stockpiles on site as well as borrow areas and soil intentionally transported from the project site.

MS-3 A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized, permanent vegetation shall not be considered established until a ground cover is achieved that is uniform, mature enough to survive and will inhibit erosion.

MS-4 Sediment basins and traps, perimeter dikes, sediment barriers and other measures intended to trap sediment shall be constructed as a first step in any land-disturbing activity and shall be made functional before upslope land disturbance takes place.

MS-5 Stabilization measures shall be applied to earthen structures such as dams, dikes, and diversions immediately after installation.

MS-6 Sediment traps and sediment basins shall be designed and constructed based upon the total drainage area to be served by the trap or basin.

A. The minimum storage capacity of a sediment trap shall be 134 cubic yards per acre of drainage area and the trap shall only control drainage areas less than three acres.

B. Surface runoff from disturbed areas that is compromised of flow from drainage areas greater than or equal to three acres shall be controlled by a sediment basin. the minimum storage capacity of a sediment basin shall be 134 cubic yards per acre of drainage area. The outfall system shall, at a minimum, maintain the structural integrity of the basin during a 25 year storm of 24 hour duration. runoff coefficients used in runoff calculations shall correspond to a bare earth condition or those conditions expected to exist while the sediment basin is utilized.

MS-7 Cut and fill slopes shall be constructed in a manner that will minimize erosion. slopes that are found to be eroding excessively within one (1) year of permanent stabilization shall be provided with additional slope stabilizing measures until the problem is corrected.

MS-8 Concentrated runoff shall not flow down cut or fill slopes unless contained within adequate temporary or permanent channel, flume or slope drain structure.

MS-9 Whenever water seeps from a slope face, adequate drainage or other protection shall be provided.

MS-10 All storm sewer inlets that are made operable during construction shall be protected so that sediment-laden water cannot enter the conveyance system without first being filtered or otherwise treated to remove sediment.

MS-11 Before newly constructed stormwater conveyance channels or pipes are made operational, adequate outlet protection and any required temporary or permanent channel lining shall be installed in both the conveyance channel and receiving

MS-12 When work in a live watercourse is performed, precautions shall be taken to minimize encroachment, control sediment transport and stabilize the work area to the greatest extent possible during construction. nonerodible material shall be used in the construction of causeways and cofferdams. earthen fill may be used for these structures if armored by nonerodible cover material.

MS-13 When a live water course must be crossed by construction vehicles more than twice (2) in any six (6) month period, a temporary vehicular stream crossing constructed of nonerodible material shall be provided.

MS-14 All applicable federal, state and local regulations pertaining to working in or crossing live watercourses shall be met.

MS-15 The bed and banks of a watercourse shall be stabilized immediately after work in the watercourse is completed.

MS-16 Underground utility lines shall be installed in accordance with the following standards in addition to other applicable criteria.

A. No more than 500 linear feet of trench may be opened at one time.

B. Excavated material shall be placed on the uphill side of trenches.

C. Effluent from dewatering devices shall be filtered or passed through an approved sediment trapping device, or both and discharged in a manner that does not adversely affect flowing streams or offsite property.

D. Material used for backfilling trenches shall be properly compacted in order to minimize erosion and promote stabilization.

E. Restabilization shall be accomplished in accordance with these regulations.

F. Applicable safety regulations shall be complied with.

EROSION AND SEDIMENT CONTROL MINIMUM STANDARDS (CONT'D.):

MS-17 Where construction vehicle access routes intersect paved or public roads provisions shall be made to minimize the transport of sediment by vehicular tracking onto the paved surface. Where sediment is transported onto a paved or public road surface, the road surface shall be cleaned thoroughly at the end of each day. Sediment shall be removed from the roads by shoveling or sweeping and transported to a sediment control disposal area. Street washing shall be allowed only after sediment has been removed in this manner. This provision shall apply to individual development lots as well as to larger land-disturbing activities.

MS-18 All temporary erosion and sediment control measures shall be removed within thirty (30) days after final site stabilization or after the temporary measures are no longer needed, unless otherwise authorized by the local program authority. Trapped sediment and the disturbed soil areas resulting from the disposition of temporary measures shall be permanetly stablized to prevent furthererosion and sedimentation.

MS-19 Properties and waterways downstream from development sites shall be rotested from sediment despositions, erosion and damage due to increases in volume, velocity and peak flow rate of stormwater runoff for the stated frequency storm of twenty-four (24) hour duration in accordance with the following standards and criteria:

A. Concentrated stormwater runoff leaving a development site shall be discharged directly into an adequate natural or man-made receiving channel, pipe or storm sewer system. For those sites where runoff is discharged into a pipe or pipe system, downstream stability analyses at the outfall of the pipe or pipe system shall be performed.

- B. Adequacy of all channels and pipes shall be verified in the following manner:
- The applicant shall demonstrate that the total drainage area to the point of analyses within the channel is one hundred (100) times greater than the contributing drainage area of the project in question; or
 - (a) Natural channels shall be analyzed by the use of a two (2) year storm to verify that stormwater will not overtop channel banks nor cause erosion of channel bed or banks.
(b) All previously constructed man-made channels shall be analyzed by the use of a ten (10) year storm to verify that stormwater will not overtop its banks and by the use of a two (2) year storm to demonstrate that stormwater will not cause erosion of channel bed or banks; and
(c) Pipes and storm sewer systems shall be analyzed by the use of a ten (10) year storm to verify that stormwater will be contained within the pipe or system.

C. If existing natural receiving channels or previously constructed man-made channels or pipes are not adequate, the applicant shall:

- Improve the channels to a condition where ten (10) year storm will not overtop the banks and a two (2) year storm will not cause erosion to the channel bed or banks; or
- Improve the pipe or pipe system to a condition where the ten (10) year storm is contained within the appurtenances;
- Develop a site design that will not cause the pre-development peak runoff rate from a two (2) year storm to increase when runoff outfalls into a natural channel or will not cause the pre-development peak runoff rate from a ten (10) year storm to increase when runoff outfalls into a man-made channel; or
- Provide a combination of channel improvement, stormwater detention or other measures which is satisfactory to the plan-approving authority to prevent downstream erosion.

D. The applicant shall provide evidence of permission to make the improvements.

E. All hydrologic analyses shall be based on the existing watershed characteristics and the ultimate development conditions of the subject project.

F. If the applicant chooses an option that includes stormwater detention, he shall obtain approval from the locality of a plan for maintenance of the detention facilities. the plan shall set forth the maintenance requirements of the facility and the person responsible for performing the maintenance.

G. Outfall from a detention facility shall be discharged to a receiving channel, and energy dissipaters shall be placed at the outfall of all detention facilities as necessary to provide a stabilized transition from the facility to the receiving channel.

H. All on-site channels must be verified to be adequate.

I. Increased volumes of sheet flows that may cause erosion or sedimentation on adjacent property shall be diverted to a stable outlet, adequate channel, pipe or pipe system or to a detention facility.

J. In applying these stormwater management criteria, individual lots or parcels in a residentia, commercial or industrial development shall not be considered to be separate developmentprojects. Instead, the development, as a whole, shall be considered to be a single development project. hydrologic parameters that reflect the ultimate development condition shall be used in all engineering calculations.

K. All measures used to protect properties and waterways shall be employed in a manner which minimizes impacts on the physical, chemical and biological integrity of rivers, streams and other waters of the state.

TABLE 6-1
GENERAL EROSION AND SEDIMENT CONTROL NOTES

ES-1: Unless otherwise indicated, all vegetative and structural erosion and sediment control practices will be constructed and maintained according to minimum standards and specifications of the VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK, and Virginia regulations VR 625-02-00 & 4VAC 50-30-40 Erosion and Sediment Control Regulations.

ES-2: The plan approving authority must be notified one (1) week prior to the pre-construction conference, one (1) week prior to commencement of the land disturbing activity, and one (1) week prior to the final inspection.

ES-3: All erosion and sediment control measures are to be placed prior to or as the first step in clearing.

ES-4: A copy of the approved erosion and sediment control plan shall be maintained on the site at all times.


ES-5: Prior to commencing land disturbing activities in areas other than indicated on these plans (including, but not limited to, off-site borrow or waste areas), the Contractor shall submit a supplementary erosion control plan to the owner for review and approval by the plan approving authority.

ES-6: The Contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by the plan approving authority.

ES-7: All disturbed areas are to drain to approved sediment control measures at all times during land disturbing activities and during site development until final stabilization is achieved.

ES-8: During dewatering operations, water will be pumped into an approvedfiltering device.

ES-9: The contractor shall inspect all erosion control measures periodically and after each runoff-producing rainfall event. any necessary repairs or cleanup to maintain the effectiveness of the erosion control devices shall be made immediately.



REVISION		DATE	No.
		###	
			###

PROJECT No:	068002
DATE	10/2014
DES.	TD/MM
DR.	MOB
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540


WOOLPERT
DESIGN | GEOTECHNICAL | INFRASTRUCTURE

PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN
CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS


EROSION & SEDIMENT CONTROL NOTES

SHEET NO.


ES1




CE




IP




IP




TP




CIP




IP




IP



CD



SF



NOTE: SILT FENCE FABRIC SHALL BE 36" TALL, STAKED WITH 2"X2"X5' HARDWOOD STAKES ON 6' CENTERS.

TABLE 3.32-E (REVISED JUNE 2003) PERMANENT SEEDING SPECIFICATION FOR COASTAL PLAIN AREA		
SEED:		
LAND USE	SPECIES	APPLICATION RATES
MINIMUM CARE LAWN COMMERCIAL OR RESIDENTIAL	TALL FESCUE:	175-200 LBS
	or BERMUDAGRASS:	75 LBS
HIGH-MAINTENANCE LAWN	TALL FESCUE:	200-250 LBS
	or BERMUDAGRASS (seed) or BERMUDAGRASS: (by other vegetative establishment method, see Std. & Spec. 3.34)	40 LBS (UNHULLED) 30 LBS (HULLED)
GENERAL SLOPE (3:1 OR LESS)	TALL FESCUE:	128 LBS
	RED TOP GRASS OR CREEPING RED FESCUE SEASONAL NURSE CROP:	2 LBS 20 LBS TOTAL 150 LBS
LOW-MAINTENANCE SLOPE (STEEPER THAN 3:1)	TALL FESCUE:	93-108 LBS
	BERMUDAGRASS: RED TOP GRASS OR CREEPING RED FESCUE SEASONAL NURSE CROP: SERICEA LESPEDEZA:	0-15 LBS 2 LBS 20 LBS 20 LBS TOTAL 150 LBS
1 - WHEN SELECTING VARIETIES OF TURFGRASS, USE THE VIRGINIA CROP IMPROVEMENT ASSOCIATION (VCIA) RECOMMENDED TURFGRASS VARIETY LIST. QUALITY SEED WILL BEAR A LABEL INDICATING THAT THEY ARE APPROVED BY VCIA. A CURRENT TURFGRASS VARIETY LIST IS AVAILABLE AT THE LOCAL COUNTY EXTENSION OFFICE OR THROUGH VCIA AT 804-746-4884 OR AT HTTP://SUDAN.CSES.VT.EDU/HTML/TURF/TURF/PUBLICATIONS/PUBLICATIONS2.HTML		
2 - USE SEASONAL NURSE CROPS IN ACCORDANCE WITH SEEDING DATES STATED BELOW:		
FEBRUARY, MARCH-APRIL..... ANNUAL RYE		
MAY 1ST-AUGUST..... FOXTAIL MILLET		
SEPTEMBER, OCTOBER-NOVEMBER 15TH..... ANNUAL RYE		
NOVEMBER 16TH- JANUARY..... WINTER RYE		
3 - MAY THROUGH OCTOBER, USE HULLED SEED. ALL OTHER SEEDING PERIODS, USE UNHULLED SEED. IF WEEPING LOVEGRASS IS USED, INCLUDE IN ANY SLOPE OR LOW MAINTENANCE MIXTURE DURING WARMER SEEDING PERIODS, INCREASE TO 30-40 LBS/ACRE.		

- FERTILIZER & LIME
- APPLY 10-20-10 FERTILIZER AT A RATE OF 500 LBS/ACRE (OR 12 LBS/1,000 SQ. FT.)
 - APPLY PULVERIZED AGRICULTURAL LIMESTONE AT A RATE OF 2 TONS/ACRE (OR 90 LBS/1,000 SQ. FT.)


- NOTE:
1. A SOIL TEST IS NECESSARY TO DETERMINE THE ACTUAL AMOUNT OF LIME REQUIRED TO ADJUST THE SOIL PH OF SITE.
 2. INCORPORATE THE LIME AND FERTILIZER INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR BY OTHER MEANS.
 3. WHEN APPLYING SLOWLY AVAILABLE NITROGEN, USE RATES AVAILABLE IN EROSION & SEDIMENT CONTROL TECHNICAL BULLETIN #4, 2003 NUTRIENT MANAGEMENT FOR DEVELOPMENT SITES. AT [HTTP://WWW.DCR.STATE.VA.US/SW/E&S.HTM#PLBS](http://www.dcr.state.va.us/sw/e&s.htm#PLBS)

TABLE 3.31-B
(REVISED JUNE 2003)
TEMPORARY SEEDING SPECIFICATIONS QUICK REFERENCE FOR ALL REGIONS

SEED	
APPLICATION DATES	SPECIES
SEPT. 1 - FEB. 15	50/50 MIX OF ANNUAL RYEGRASS (LOLIUM MULTI-FLORUM) AND CEREAL (WINTER) RYE (SECALE CEREALE)
FEB. 16 - APR. 30	ANNUAL RYEGRASS (LOLIUM MULTI-FLORUM)
MAY 1 - AUG. 31	GERMAN MILLET

- FERTILIZER AND LIME
- APPLY 10-10-10 FERTILIZER AT A RATE OF 450 LBS/ACRE (OR 10 LBS./1,000 SQ. FT.)
 - APPLY PULVERIZED AGRICULTURAL LIMESTONE AT A RATE OF 2 TONS/ACRE (OR 90 LBS./1,000 SQ. FT.)

- NOTE:
1. A SOIL TEST IS NECESSARY TO DETERMINE THE ACTUAL AMOUNT OF LIME REQUIRED TO ADJUST THE SOIL PH OF SITE.
 2. INCORPORATE THE LIME AND FERTILIZER INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR BY OTHER MEANS.
 3. WHEN APPLYING SLOWLY AVAILABLE NITROGEN, USE RATES AVAILABLE IN EROSION & SEDIMENT CONTROL TECHNICAL BULLETIN #4, 2003 NUTRIENT MANAGEMENT FOR DEVELOPMENT SITES. AT [HTTP://WWW.DCR.STATE.VA.US/SW/E&S.HTM#PLBS](http://www.dcr.state.va.us/sw/e&s.htm#PLBS)



REVISION

DATE

PROJECT No: 068002

DATE 10/2014

DES. TO/MM

DR. MOB

CKD. JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540



PUMP STATION 134 & 123
FORCE MAIN MAINTENANCE PLAN

CITY OF HAMPTON, VIRGINIA
PUBLIC WORKS

EROSION & SEDIMENT CONTROL DETAILS



SHEET NO.

ES2

last Saved By: tschenkov, 9/3/2014 2:11:32 PM
 layout Tab Name: T1; Images: , Xrefs: 68002_TBLK.dwg
 Plot Path: C:\Users\Brien\OneDrive\Documents\68002_MOT.dwg
 Plotter: Maxwell Plotted: March 31, 2015, 9:06:04 AM

- COMPANY NAME & PHONE NUMBER;
COMPANY REPRESENTATIVE & PHONE NUMBER;
BRIEF DESCRIPTION OF WORK INVOLVED;
PROPOSED START DATE & APPROVED WORK HOURS; AND
EXPECTED COMPLETION DATE.

FOR A DETOUR PLAN HAS BEEN SUBMITTED AND APPROVED FOR A ROAD CLOSURE, A SIGN READING **"NOTICE - ROAD - WILL BE - CLOSED - (DATE) TO (DATE)"** IN BLACK LETTERS ON AN ORANGE BACKGROUND SHALL BE POSTED ON EACH APPROACH, AT THE POINT WHERE THE ROAD WILL BE CLOSED FOR A PERIOD OF NOT LESS THAN ONE WEEK PRIOR TO CONSTRUCTION. INSTEAD OF THE AFOREMENTIONED STATIC SIGN, THE CONTRACTOR MAY USE PCMS BOARDS TO DISPLAY THE REQUISITE INFORMATION ELECTRONICALLY.



PROJECT No:	068002
DATE	10/2014
DES.	TD/MM
DR.	MOB
CKD.	JBE

676 Independence Parkway
Suite 100
Chesapeake, VA 23320
757.549.3549
FAX: 757.549.3540



WOOLPERT
DESIGN | GEOSPATIAL | INFRASTRUCTURE

SHEET NO.	<p>PUMP STATION 134 & 123</p> <p>FORCE MAIN MAINTENANCE PLAN</p> <p>CITY OF HAMPTON, VIRGINIA</p> <p>PUBLIC WORKS</p>
	<p>TRAFFIC CONTROL NOTES AND DETAILS</p>

T1